



REDDOT GLOBAL Studio

"Making your dream space a reality"

Quote/10/04/2026/Mr.Kalyan

S.No	Description	Finesh	Description	L	B	Area	No	Price	Amount
1	Wood Work								
	Providing and Fixing BWP water proof & Termite proof plywood along with half white 0.8mm laminate indside of the Carcass and balance as follows (Modular finish)								
1.1	Kitchen	Box	East Side Base Unit	10.2	2.64	26.928	1	2000	53856
a		Box	East Side Wall Unit	7.24	2	14.48	1	2000	28960
b		Frame	East Side Loft	10.2	2.23	22.746	1	1200	27295.2
c			East Side Loft Bottom Plank	10.2	2	20.4	1	700	14280
d		Box	West Side Base unit	5.93	2.64	15.6552	1	2000	31310.4
e		Box	West Side Wall unit	5.93	2	11.86	1	2000	23720
f		Box	West Side Tall unit	2.15	6.67	14.3405	1	2000	28681
g		Frame	West Side Loft Unit	13.16	2.23	29.3468	1	1200	35216.16
h			West Side Loft Bottom Plank	13.16	2	26.32	1	700	18424
i			Tandoms				7	5500	38500
j			Bottle Pull Out				1	3500	3500
k			Profile Strs				5	4000	20000
l			Gola Profile				3	3000	9000
1.2	Pooja	Box	Pooja Box	3	6.67	20.01	1	2000	40020
a			Pooja CNC				1	2000	2000
b			Pooja Box Profile				2	8000	16000
c			Drawers				2	3500	7000
1.3	Arch Panelling		Panelling	1	7.3	7.3	1	700	5110

a			Panelling	1	7.3	7.3	1	700	5110
b			Panelling	1	7	7	1	700	4900
1.4	Bar Counter	Box	Bar Counter	4.94	7	34.58	1	1650	57057
a			Bar Counter Profile Strs				2	8000	16000
1.5	Vanity	Box	Vanity	3.46	2	6.92	1	1650	11418
1.6	TV Arch Panelling		Panelling	1	8.9	8.9	1	700	6230
a			Panelling	1	8.9	8.9	1	700	6230
b			Panelling	1.5	8.9	13.35	1	700	9345
1.7	Hall TV	Box	TV Box	7.9	1.32	10.428	1	1650	17206.2
a			Drawers				4	3500	14000
b			Tall Box	1.32	7.41	9.7812	1	1650	16138.98
c			Panelling	9.87	8.89	87.7443	1	800	70195.44
1.8	MBR	Box	Wardrobe	7.9	8.56	67.624	1	1650	111579.6
a			Window Sitting Box	4.2	1.65	6.93	1	1650	11434.5
b			Two Door Sliding Track&Kit				1	5000	5000

Sub Total 764717.48

GST 18% Extra

Grand total

Terms & Conditions

- 1 The above price is inclusive of labour and all required materials
- 2 Power and water should be provide at site for free of cost
- 3 Any Additional work out of quotation will be charged accrodngly
- 4 Floor matt & Deep cleaning charges extra
- 5 One year service warranty for any defects in workmanship, and warranty given by brands will carry forward

Material Specification

2 Wood Work :

a Vrishan Ply - BWP 710 Grade Gurjon with water and termite proof plywood 16mm,6mm

3 Laminates :

a Laminate 1mm HGL & Internal 0.8mm Laminates

b 0.8 mm thickness Laminates for inside the carcase

c Edge banding tapes with different specifications Factory Finish

4 Kitchen :

a Vrishan Ply 710 Grade 16MM.6MM 1 MM High Gloss Laminate for shutters Factory Finish

b Premium Hardware Hettich/Ebco make tandom baskets with softclose function

c	Premium Hardware: Hettich, Ebco
5 Glass :	
a	Saint Gobain
6 Handles	
a	Premium Handles range < 250/-
Payment Details:	
*	50% shall be paid as advance amount to start production
*	40% shall be paid at the time of dispatch of material
*	10% after completion of work
*	Delivery time is 15 days after receipt of advance and depending on
*	availability of material and erection time shall be 30 to 45 days